

5000147960 Ornamental Fencing



Augusta's Custom Fab and Build Inc.

+15048585855
theo@augustafabandbuild.com
2308 Hero Dr
Gretna, LA
70053-7424

LSLB

American Welding Society 140353437
Commercial Insurance IBL-F3N4BNVU3C

COVID MEMORIAL PARK FOR JEFFERSON PARISH DEPARTMENT OF PARKS AND RECREATION

5047366999
JPRecreation@jeffparish.net
7437, Lapalco Boulevard
Marrero, LA
70072

Estimate Number 220
Date Feb 06, 2024

Item	Quantity	Price	Total
Metal Fencing (80) Pinched Rails 24ft (1476) 1/2" Picket Toppers (374) 1/2" Pickets 24ft (73) 3x3 Post 8ft (73) 3x3 Post Caps (2) 2x2 tubing 24ft (4) Heavy Duty Barrel Hinges (6) 5 gallon Black Gloss (2) 5 gallon Red Primer (no taxes)	1	\$26,768.32	\$26,768.32
Time and Labor(Fabrication and Installation) Weather May Affect Paint Time But Will NOT AFFECT PRICING -Fencing will be Fabricated in 7' to 8' panels. -Each 3x3 Post will Be 2' subsurface. -Pickets will be 4" on center. -1 Flur De Lis will be on Each 1/2" picket. -All Materials to be Painted Gloss Black -1 Doulbe Swing Gate to be Fabricated and Installed (no taxes)	140	\$80.00	\$11,200.00
			\$37,968.32
State:			8.5% \$0.00
Total:			\$37,968.32
Deposit Due:			\$28,688.32
Balance:			\$37,968.32

Job Is Priced at 3 Weeks of Work

- (WEEK 1) Demo and Setting Post in Chainwall
- (Week 2) Fabricating, Painting, and Installing Fencing Panels
- (Week 3) Installing Panels and Closing out Job

12 month warranty on all welding and 6 month warranty on all repair
(NOT INCLUDING MATERIALS)

DEPOSIT:
100% Materials Prices
24 hours time and labor