

MOREHOUSE PARISH SCHOOL BOARD

Specifications for Bleachers at Delta Jr. High School

- 1) Furnish all materials and labor to remove old bleachers from both sides of gym at Delta Jr. High School. Remove and dispose of all debris.
- 2) Provide, deliver, and install two banks of 95 feet by 9 rows high, wall-attached telescoping bleachers with three phase friction power, 10¼" rise, 24" spacing, 10" sculptured seat modules, forward folding, NFPA foot level aisles with intermediate steps, self storing aisle rails, self storing end rails, 18 column cutouts, and standard handicap notchouts without rails as required by the ADA. Note: Color to be chosen by school.
- 3) Provide all materials and labor for all electrical work required for installation of new bleachers.
- 4) Guarantee and warranty installation for a minimum of five years.

The dates of removal of the old bleachers and the installation of the new bleachers will have to be coordinated with the General Foreman and the School Principal.

Quote

Contractor Name: Hahn Enterprises, Inc.

Address: P.O. Box 19495

New Orleans, LA 70179

Contact Person: Tania Hahn, Jamai Hill

Telephone Number: 504-488-3536

Tax ID Number: 72-1488372

Do you have worker's compensation insurance? YES

Bid Amount: \$ \$93,868.00