



Project Proposal
Bid # 50131289

July 16,2020

Customer: Jefferson Parish Park and Rec

Location: Mike Miley Stadium

PROJECT SCOPE

Provide all labor, equipment, and materials install new netting from end of dugout to dugout to roof (approx. 150' x 28.5') 2 nd pc of netting to be placed above roof on existing structure. (8' x 150) extend netting from existing chain link on 3rd base line to double gate at matching height of 20' (approx. 125'). Using #18 Plateena netting.. Additional pole on 3rd baseline installed by others. According to bid documents ALL support structure will remain and old chain link will be removed by others.A new wall will be built by others at bottom for net to be attached per Brad Roth (JPPR)Installation includes a two year warranty.

Furnish and Install the following:

- Approx 7,350 sq. ft. of **# 18 Plateena Baseball netting** polyester with 3/8" rope border . Netting includes a Five year manufacturer's warranty.
- 250 cadmium steel attachment snaps.
- All supporting bolts, washers, clamps, and other hardware which all conform to the specifications of one or more of the following: **ANSI, ASTM, IEEE, NEMA**
- All labor, equipment, and shipping charges included.

Scope Cost \$ 27,965.00

Exclusions and Clarifications:

- *NET Connection will not be held responsible for any of the existing structure .*
- Any responsibility for damage to turf, driveways, parking lots, irrigation systems, and drainage systems, caused by equipment required to perform our work.
- Any costs for permitting, expediting, licensing, etc. will be passed along to the owner
- Any costs due to delays in our work caused by site conditions or work by other contractors will be passed along to the owner plus 10%.
- Any responsibility for ball containment, height and placement of netting is solely the customer's decision.
- NO tax considerations are included in the Scope Cost.

Terms: Per contract.

A 1-½ % penalty applied for all balances beyond 30 days. 18% per annum.