

Concordia Parish School Board

801 Ee Wallace Blvd S, Ferriday, LA, 71334

Scope of Work

FIRE ALARM SYSTEM.

JCI to reuse existing silent knight 5208 fire alarm panel & install new field devices in renovation area.

This system will include:

- New smoke & heat detectors are installed at marked locations in renovation area.

The existing fire alarm system shall monitor & control all existing & new initiating devices and notification devices.

The existing fire alarm system shall communicate to the monitoring station via an existing external cellular dialer.

This building is fully sprinklered.

New wiring shall be installed for newly added devices.

Newly added devices are linked to nearest available existing devices.

Existing device locations, types & manufacturing will be required at permitting. Failure to provide this information will delay design completion.

This quote includes estimated sales tax only. Any additional taxes, duties, tariffs or similar items imposed prior to shipment will be charged.

Clarifications

1. Any modifications or additions required by the local AHJ shall require a change order directive.
2. The existing fire alarm control units shall be connected to dedicated 120VAC power circuits that shall be supplied by a customer-supplied electrical contractor.
3. The existing fire alarm communicator shall be connected to a dedicated 120VAC power circuit that shall be supplied by a customer-supplied electrical contractor.
4. We have considered drop tile ceiling height as 8' to 10' & assuming 10' ladder will be sufficient to complete all work.
5. Provisions have been made in the estimate for a PE Stamp.
6. The permit cost calculated as per compass guidelines.
7. Based on the received input details we have added new devices in renovation area at marked locations.
8. According to the received plans, the fire alarm scope of work includes the first and second-floor elevators & the elevator lobby.
9. The existing water flow and tamper switches will be monitored by the existing fire alarm panel zones.
10. We have considered building is fully sprinklered.

Exclusions

1. We have not included any interfaces for elevator recall, as it is considered out of scope.
2. We have not included any notifications at the elevator lobby because of its plan and spec job.