

POST OFFICE BOX 215 AMITE, LOUISIANA 70422 OFFICE (985) 748-3211 FAX (985) 748-7576

## ROBBY MILLER PARISH PRESIDENT

## **NOTICE TO BIDDERS**

NOTICE IS HEREBY GIVEN THAT SEALED BIDS WILL BE RECEIVED BY THE TANGIPAHOA PARISH GOVERNMENT UNTIL WEDNESDAY, DECEMBER 13, 2017 AT 10:00 A.M. IN THE TPC CHAMBERS, 206 E. MULBERRY STREET, AMITE, LOUISIANA ON THE FOLLOWING:

WASHED GRAVEL **HEAVY RED CLAY** CORRUGATED METAL CULVERTS **BRIDGE MATERIALS** JANITORIAL SUPPLY STEEL SLAG

**HOT MIX & COLD MIX** FILLED DIRT & SAND SIGN POST **FUEL** PEST CONTROL

THEN AND THERE BIDS WILL BE OPENED AND READ ALOUD. BIDS RECEIVED AFTER THE SPECIFIED TIME AND DATE WELLNOT BE OPENED OR RECOGNIZED.

SPECIFICATIONS MAY BE PICKED UP OR REQUESTED BY PHONE AT THE OFFICES OF THE TANGIPAHOA PARISH GOVERNMENT, BETWEEN THE HOURS OF 8:00 A:M. & 4:00 P.M., MONDAY THRU FRIDAY.

TANGIPAHOA PARISH GOVERNMENT BID DOCUMENTS ARE POSTED ON www.centralbidding.com.

THE TANGIPAHOA PARISH GOVERNMENT RESERVES THE RIGHT TO REJECT BIDS IN ACCORDANCE WITH THE LAW.

> S/DONNA DOMIANO PURCHASING AGENT

DAILY STAR PLEASE PUBLISH NOVEMBER 14, 21, & 28, 2017 **TANGIPAHOA PARISH GOVERNMENT** 

**BID OPENING DECEMBER 13, 2017** 

LIMESTONE BASE COLD MIX

\*\*\*\*\*CONTRACT SHALL BE FOR A PERIOD OF ONE (1) YEAR, BEGINNING JANUARY 1, 2018 AND ENDING DECEMBER 31, 2018.\*\*\*\*\*

ADDRESS! BOLIBS FOL Allen, LA TOLET

TYPE D MIXTURE - ALTERNATE 2: 43

\_\_PER TON DELIVERED.

Min. 24 ton delivered

SIGNATURE

DATE: 12/13/17

TYPE D Mixture-Alternate 2: The binder shall be an asphalt emulsion and meet the following specification requirements:

## Physical Properties:

	a 180	Minimum	<u>Maximum</u>
1) 2) 3) 4)	Flash Point, Tag Open Cup	200F, 80.0 100 90.0	90.0 Pumpable
Test of	n Residue from Distillation to 500F:		
1) 2) 3)	Oil Distillate, %, ASTM	4.0 500 98.0	8,000

## Stone Coating Text A

- 1) Weigh 200.0g dry aggregate (Agg. to be used on project) into a beaker.
- 2) Weigh 4.0g tap water into the beaker containing the dry aggregate and mix for 30 seconds.
- Weight 10.0g of eight Pave Magic or Patch Magic into the beaker containing the damp aggregate and mix vigorously for 120 seconds.
- 4) Dump contents of beaker onto suitable surface and visually check coating of aggregate. There shall be no evidence of asphalt run-off.